



"You Want to Do What?" Managing Risk for a First-of-its-kind Project

LASALLE CANAL MGP SITE



Dave Lowry (AECOM), Andy Burkemper (AECOM) & Dave Palmer (Ameren)

November 22, 2019

Agenda

1

Introduction to MGP & Ameren's MGP Program

2

The LaSalle Canal Project – Identifying Issues

3

The LaSalle Canal Project – Finding a Solution

4

The LaSalle Canal Project – Getting to Approval

5

The LaSalle Canal Project – Managing Risk During Implementation

6

Q&A

Introduction to MGP

Manufactured Gas Plants (MGPs)

- Common from early 1800s to mid 1900s
- Converted coal/oil to gas for use in lighting, heating & cooking
- One in every city, up to 5,000 sites nationwide
- Produced various byproducts, including coal tar
- Ultimately replaced by natural gas
- Modern environmental liability



Ameren's MGP Program

- 55 former MGP sites in 3 states
- Started on identification, investigation, & remediation in 1986
- Currently working on a portfolio of 16 sites in Illinois
- Objective to achieve closure on all sites by 2023
- Historic approach to site remediation centered on excavation & landfilling
- Expanding review of options for remedy selection




Ameren's MGP Program

LaSalle Canal Project Site Overview

I&M Canal Opened in 1848

97 Miles Long

Chicago to LaSalle/
Peru Linked Great Lakes
to Gulf of Mexico



60' Wide x 6' Deep
Barges Towed by Mules
Series of 15 Locks
Replaced by Chicago
Sanitary & Ship Canal in
1933




LaSalle MGP Site Located Below Last Lock of I&M Canal
Operated From 1903 to 1943
Coal Tar Impacts Found in Canal
Canal Site is 250' Wide by 3,100' Long & 17.5 Acres
Water Depth Depends on River Stage & Zero to 20'+ Deep


The LaSalle Canal Project – Identifying Issues (2004-2015)

Investigation Summary

- Sediment sampling
 - 469 samples from 138 borings
 - Geoprobe®, HSA, HA, Vibracore
 - Lab analyses
 - Chemical, forensic, geotechnical
- TarGOST (Tar-specific Green Optical Screening Tool)
 - 118 locations, ~23' deep




The LaSalle Canal Project – Identifying Issues



The LaSalle Canal Project – Identifying Issues

Site Investigation/Impact Delineation



The LaSalle Canal Project – Identifying Issues

Multiple Stakeholders & Multiple Stakeholder Interests

- **Ameren** – remove future environmental liability associated with MGP impacts
- **IEPA** – remedial action that results in an acceptable level of risk to ecological & human health
- **IDNR** – enhance the possible use options of the natural resource; minimize negative impacts to the natural resource while remedial action is ongoing
- **City of LaSalle** – enhance options for public & private use of the canal; no impact to City's existing wastewater management system
- **Neighboring Facilities/Property Owners** – no negative impacts to their operations



PMBOK®


PROJECT STAKEHOLDER MANAGEMENT

- Identify stakeholders
- Stakeholder management/communications plan
- Control stakeholder engagement (communications, permitting, formal agreements)

Addressing Multiple Interests Often Increases Complexity of Project/
Project Design, Thereby Increasing Number of Project Risks

The LaSalle Canal Project – Identifying Issues


- Bank stability
- Overhead & underground utilities
- Significant water level fluctuation
- Constrained support area
- Navigable waterway within canal



The LaSalle Canal Project – Finding the Solution

(2016-2018)

Now What? What Is The Path to An Ameren Approvable Project?



The LaSalle Canal Project – Finding the Solution

Initiated an Extensive Remedial Action Alternatives Analysis

Excel Spreadsheet Created to Facilitate Analysis of Various Options

- >10 remedial options with alternative approaches considered
 - Leave all impacted sediment in place & cap
 - Excavate all impacted sediment
 - Solidify all impacted sediment (ex-situ & in-situ options)
 - Utilize various available human health & ecological risk analysis/modeling
 - Combinations of all of the above
 - Etc.
- 26 outcomes evaluated for each remedial option
- Spreadsheet produced a score for seven stakeholder decision areas

16,203+ ▲
7,410+ ▲
4,991+ ▲
2,007+ ▲



PMBOK®

PLANNING PROCESS GROUP

- Those processes performed to establish the total scope of effort
- Define & refine the objectives
- Develop the course of action to attain objectives

The LaSalle Canal Project – Finding the Solution

Alternatives Analysis

Remedial Objective & Method Base	Removal of MGP-Related Impacts AND Engineered Capping		Removal, Stabilization, and Capping	Engineered Capping					RFP Scope
OPTION	M	N	O	S	T	U	V	W	X
Remediation Scenario	Removal of Primary Impacts to 10'. Capping the excavation footprint and Secondary Impacts >22.8 ppm in top 5'	Removal of All Primary Impacts to 10' and 70% from 10-15'. Capping the excavation footprint and Secondary Impacts > 22.8 ppm in top 5'	Removal of Primary Impacts to 10'. Stabilizing the remaining primary impacts and capping Secondary Impacts >22.8 ppm in top 5'	Removal of Impacts to Navigable Width and Depth and Capping Pool and Channel and Cap All Secondary Impacts >22.8 ppm in Top 5'	Cap Area(s) of Existing Exposure Risk (Secondary Impacts >22.8ppm) in Top 5'	Remove 2' and Cap Area(s) of Existing Exposure Risk (Secondary Impacts >22.8 ppm) in Top 5'	Cap Entire Area	Remove 2' and Cap Entire Area	Stabilize banks and remove impacts through the middle of the Canal. Benthic cap as restoration cover layer.
Removal Depth ²	Shallow	Moderate	Shallow	Shallow	NA	Shallow	NA	Shallow	Moderate
Impacts Removed	Primary	Primary	Primary	(Removal not impact-based)	NA	NA	NA	NA	Primary
Impacts Capped	Secondary>22.8ppm	Secondary > 22.8ppm	Secondary >22.8ppm	Secondary >22.8ppm	Secondary >22.8ppm	Secondary >22.8ppm	All	All	Cap not impact based

Stakeholder Requirement Rankings	Relative Cost	8	11	12	10	2	4	3	7	14
	Exposure	13	9	11	14	20	16	18	15	7
	Remaining Liability	13	12	3	16	22	20	21	17	5
	Navigability	14	12	13	2	18	17	22	16	6
Overall	Raw Score	48	44	39	42	62	57	64	55	32
	Raw Rank	13	11	7	10	19	17	20	15	3
	Cost-Weighted Score	64	66	63	62	66	65	70	69	60
	Cost-Weighted Rank ⁴	7	9	5	4	9	8	13	11	3

The LaSalle Canal Project – Finding the Solution

Project Risk Register – Version 1

- **49** project risks identified
- Financial impact of all risks ~**\$22M**

* Engineer's estimate of total project cost = \$38M

Risk Management Register														Risk Level		Legend		Probability	
Item	Project Phase	Risk Status (S)	Risk Category (P, I, O, S, R)	Potential Impact (Conseq and Effect)	Risk Response Strategy	Triggers (Indicators that the risk will occur)	Estimated Schedule Impact (days)	Maximum Exposure	Estimated Exposure (Contingency)	Action Owner (S)	Start Exposure	End Exposure	Impact	Probability	Risk Rank (S)	Contingency (S)	Risk Indicator: % of Contingency vs Risk Rank (S)		
1	Design	Closed	Regulatory	Stakeholders (i.e., ILPA, DNR, etc.) don't agree with pre-delineated approach of sediment removal with no confirmation samples	Reevaluate remedial approach to consider confirmation sampling or other alternatives	Stakeholder disagreement of one-delineated approach	90	\$250,000	\$0	Design Consultant	05/01/17	08/31/17	4	3	1	0	0%	0.00	
2	Design	Closed	Regulatory	Stakeholders (i.e., ILPA, DNR, etc.) don't agree to passive remedial approach (i.e., property restrictions) to the east of the remedial area	Reevaluate remedial approach to consider active remediation in eastern area or other alternatives	Stakeholder disagreement of eastern area approach	90	\$750,000	\$0	Design Consultant	05/01/17	08/31/17	3	3	0	0	0%	0.00	
3	Design	Open	Regulatory	Approval for MOU and/or RFP delays schedule	Initiate approval process early	Failure to receive approval letters by scheduled date	45	\$10,000	\$250	Design Consultant	06/02/17	11/01/17	2	2	2	4	0%	0.00	
4	Design	Open	Schedule	Need to obtain required permits before desired work start dates (currently 04/17/17)	Submit O&E permit application no later than 11/15/17 Submit for permit applications no later than 1/15/18	Failure to receive permit correspondence by scheduled date	30	\$50,000	\$6,250	Design Consultant	06/02/17	02/28/17	3	3	2	0	0%	0.01	
5	Design	Open	Schedule	Quality Liquid Feeds (QLF) series presents use of former Main Site property as a support area during Canal Site remediation, reducing the land available for remedial support	Reevaluate land support requirements and layout - Use and final barges within canal to stage and collect hydroxide dredged sediment	QLF refusal to sign appropriate access agreement with Ameren	90	\$500,000	\$52,500	Design Consultant	06/02/17	10/02/17	3	3	3	2	0	1%	0.05
7	Design	Accepted	Operational Impact	Changes in sewer force main design exceed existing capacity for pumps	New pump will be required	Design calculations indicate that the proposed design for the sewer force main will exceed the existing pump capacity		\$187,000	\$68,865	Design Consultant	06/02/17	05/01/17	1	2	3	5	10	3%	0.25
8	Design	Accepted	Performance	Water turbidity during dredging operations exceeds allowed limits	Performance based specification requiring turbidity curtains around dredge work areas as contingency measure	Turbidity monitors indicate issue		\$52,500	\$1,313	Design Consultant	06/02/17	05/01/17	1	2	5	10	1	0%	0.00
9	Remediation	Open	Performance	Water turbidity during dredging operations exceeds allowed limits following implementation of initial contingency measures	Reduce rate that dredging is occurring	Turbidity monitors indicate issue				Construction Manager	06/02/17	05/01/17	1	2	5	10	1	0%	\$VALUE
10	Design	Accepted	Construction	Sediments are not able to pass required stabilization quality controls following ISS	Perform bench-scale study using colloid-stabilized samples from canal to confirm additive type and mix ratio to determine material types and mix ratios that will achieve required UC parameters	Test results at time of ISS result in UCS and hydraulic conductivity values below UC requirement		\$11,000	\$275	Design Consultant	06/02/17	05/01/17	3	2	5	15	1	0%	0.00



PMBOK® IDENTIFY RISKS

- Brainstorming
- Assumptions analysis
- Influence

PMBOK® OUTPUT: RISK REGISTER

- List of project risks
- Identified potential responses
- Probability & impact
- Risk categorization



The LaSalle Canal Project – Finding the Solution

“You Want to Do What?” – Actual Quote from Ameren Leader



PMBOK®

PLAN RISK RESPONSES

- The process of developing options & actions to enhance opportunities & to reduce threats to project objectives

The LaSalle Canal Project – Finding the Solution

Advantages


- Provides opportunity for regular review, input & buy-in from multiple stakeholders from concept to final stages
- Progressive design with constructability review leads to progressively increasing cost & schedule certainty
- Project risks identified early & often
- Design process considers risk response strategies (e.g., avoid, transfer, mitigate, accept, etc.)
- Contractors have input & responsibility for 95% design package



PMBOK®

PROJECT MANAGEMENT PROCESSES

- “The application of the project management processes is iterative, & many processes are repeated during the project”
- “The Define Scope process can be highly iterative”
- “The iterative nature of project management means that the processes from any group may be reused throughout the project life cycle”
- An iterative process, because new risks may evolve or become known as the project



The LaSalle Canal Project – Finding the Solution

First Action . . . Need a Second Alternatives Analysis

- Further evaluate top four options & various available combinations
- Incorporate a cursory evaluation of some key risks identified



PMBOK®
PROJECT RISK MANAGEMENT
IDENTIFY RISKS

- Brainstorming
- Expert judgement

QUALITATIVE RISK ANALYSIS

- Risk urgency assessment
- Risk categorization

The Outcome . . .


- In-situ sediment stabilization, along with dredging

Remediation Alternative Analysis														
Objective	Measure	Weight	Alternative # 1 - Excavate and dispose impacted sediment above the RO			Alternative # 2 - In-situ physical or chemical stabilization/solidification of impacted sediment above the RO			Alternative # 3 - Excavate and dispose impacted sediment above the RO to an elevation of 432'. Place permeable reactive barrier over impacted sediment present below an elevation of 432' that is above the RO.			Alternative # 4 - Excavate and dispose impacted sediment above the RO to an elevation of 432'. Perform IS of impacted sediment below an elevation of 432' that is above the RO.		
Enhances ecological/recreational value of site		Must	Yes*			No			Yes*			Yes*		
Allows for the possible future use as an access to Illinois River or marina		Must	Yes*			No			Yes*			Yes*		
Safety	Adhere to Amersol Rules to Live By and AECOM Life Preserving Principles	Must												
Permanent remedy that reduces long-term risks and O&M requirements		10	10	100		7	70		6	60		8	80	
Minimize impact of canal water level fluctuations on construction schedule		7	3	0		8	56		3	0		6	42	
Minimize construction schedule duration	Number of calendar days	8	5 to 6 weeks (two shifts, 7-days)	5	40	300-700 cy/day	8	64	300-700 cy/day	6	48	300-700 cy/day	7	56
		6	Mixing performance is better in tension. Delamination concerns. Humidity, temperature, and moisture affect installation.	10	60	Mixing performance is in tension, not compression. Delamination concerns. Humidity, temperature, and moisture affect installation.	5	30	Less impacts due to temperature and humidity. Shrinkage and delamination concerns.	8	48	Does not require foot pipe for structural support. Surface can be wet before.	9	60
Maximize ability to leverage a proven solution	Confidence in solution	6	Can carry the railroad load at the damaged section.	10	60	Cannot carry the load at the RR damaged section w/o CFRP.	6	36	Cannot carry the load at the RR damaged section w/o CFRP. Concerns on our quality control/delimiting/delays.	6	36	Can carry railroad load at damaged section	9	54
Minimize operational interruptions to Material Handling	Fuel supply or bi-product flows (sulfur, slag etc.)	4	5 to 6 weeks. Impacts to track # 4.	7	28	4 to 5 weeks. Impacts to track # 4.	8	32	35 weeks. Impacts to track # 4.	10	40	4 weeks. Impacts to track # 4.	9	36
Maximize ability to withstand future loads (weight above pipe) ash, RR tracks and equipment	Surcharge capacity and live load (trains)	1	Can carry the railroad load at the damaged section.	10	10	Cannot carry the load at the RR damaged section w/o CFRP.	6	4	Cannot carry the load at the RR damaged section w/o CFRP. Concerns on our quality control/delimiting/delays.	6	4	Can carry railroad load at damaged section	9	10
	Higher weight (not used)	4												
Final Score				432			511			511			600	
Rank				4			5			2			1	

The LaSalle Canal Project – Finding the Solution


Design Challenges

- ✓ Bank stability
- ✓ Navigable waterway within canal
- TBD – overhead & underground utility issues
- TBD – significant water level fluctuation
- TBD – constrained support area



ISS to Provide for Bank Stability & Concurrently Solidify & Immobilize Contaminated Media
Dredging to Address the Desire for a Navigable Waterway, & Removal of Contaminated Media

The LaSalle Canal Project – Getting to Approval



**YOU ARE
HERE**
May, 2017




PMBOK®
RISK STRATEGIES

- Avoid
- Transfer
- Mitigate
- Accept

The LaSalle Canal Project – Getting to Approval


ISS

Bank stability; contaminated media solidification




Property access agreements

Work area adjacent to canal



Dredging

Navigable waterway; removal of contaminated media



The LaSalle Canal Project – Getting to Approval



Ameren LaSalle Canal Sediment Remediation Project

Bid Specification

Table of Contents

Bid Specification Instructions

Bid Forms:

- Schedule A – Schedule of Quantities and Prices
- Schedule B – List of Addenda
- Schedule C – Schedule of Materials - (Variations and Sources)
- Schedule D – List of Subcontractors
- Schedule E – List of Equipment
- Schedule F – Qualification of Contractor and Personnel
- Schedule G – Alternative Bid Proposals
- Schedule H – Contractor Bid Certification Form

Issue for Bid Drawings and Specifications:

- Design Drawings
- Technical Specifications

Attachments:

- Attachment A: Treatability Study
- Attachment B: Geotechnical Engineering Report
- Attachment C: Approved Ameren Disposal Facilities
- Attachment D: Preliminary Schedule
- Attachment E: December 2017 Photographs of LaSalle Canal (Visual Debris Survey)
- Attachment F: Ameren Diverse Vendor List
- Attachment G: Lime Kiln Dust Specification
- Attachment H: Plat of Survey
- Attachment I: Environmental Investigation Analytical Data
- Attachment J: Historical Boring Logs (In addition to Geotechnical Engineering Report)
- Attachment K: Local Notice to Mariners Entry Request Form
- Attachment L: Access Agreements
- Attachment M: Historical River Stage Elevations

Contractor Bid Evaluation & Scoring

- 27 separate criteria evaluated
- Evaluated outcome with & without weighting of various critical items
- Performed a separate cost sensitivity analysis




PMBOK®

ACQUIRE PROJECT TEAM

- Negotiation
- Acquisition
- Multi-criteria decision analysis

The LaSalle Canal Project – Finding the Solution

“Approved” – Actual Quote from Ameren Leader




The LaSalle Canal Project – Managing Risk During Implementation



The LaSalle Canal Project – Managing Risk During Implementation



The LaSalle Canal Project – Managing Risk During Implementation



The LaSalle Canal Project – Managing Risk During Implementation



RISK



Release/Impact to Illinois River

- Elevated canal water pH – fish kill
- Elevated turbidity
- Free phase coal tar/water sheen

MITIGATION



- Cofferdam
- Moonpool/turbidity curtain
- Buoy monitoring system
- pH adjustment system
- Oil boom/pom poms

RESULT



- Risk-based contingency value ~ \$640,000
- Contingency used ~\$310,000

The LaSalle Canal Project – Managing Risk During Implementation



RISK

- Landfill halts/refuses receipt of waste



MITIGATION

- Bid requirement
- Landfill agreement requirement
- Identification of multiple landfill options



RESULT

- Risk-based contingency value = \$215,000
- Contingency used = \$0



AECOM

Q & A



Thank You!

Dave Lowry, AECOM
T 314-802-1176
E dave.lowry@aecom.com

Andy Burkemper, AECOM
T 314-743-4175
E andrew.burkemper@aecom.com

Dave Palmer, Ameren
T 314-554-2108
E DPalmer2@ameren.com

